Point A
1. Towards Longstock add sign below pedestrians sign saying "for 1 ½ mile"
2. Refresh SLOW at each bend sign
3. Change chevrons for yellow bordered signs
4. Virtual footway 1.5m between bend signs
5. opposing side edge of carriageway mark

Points B1 & B2 are identical locations so B1 applies to B2
1. Introduce SLOW either side of the vehicular entrance
2. Virtual footway 1.5m on playground side 50m either side of junction
3. opposing side edge of carriageway mark same distance

Point D
1. Church Road is private after the last property
2. Bright sunlight will temporarily blind drivers in certain conditions.
3. When leaving the junction good visibility is seen from the left but impaired looking right. Consider a junction ahead sign on Longstock Road and re fresh road markings.

Point C
1. Introduce edge lining either side where applicable between Longstock Rd and terminal speed limit point by The Willows
2. Add 30mph roundel adjacent to terminal speed limit by The Willows
3. Advise structures section of issue raised by Parish

Point F
1. Refresh road markings on triangular entrance to Bottom Road
2. Erect horse and rider sign near to Brooks Farm along either side on Longstock Road and near to the terminal speed signs west along Bottom Road
3. Consider on two posts a village sign along Bottom Road.

Point E
1. There is sufficient signing along this highway to advise motorists of the conditions
2. To satisfy the allegation of speeding motorists a speed survey would be requried.
3. Consider on western side 1.5m virtual footway and edge of carriageway on opposite side

Point G
The constraints shall be as outlined by the parish in their notes
1. Consider edge of carriageway markings along the western side
2. Consider a Virtual footway 1.5m along eastern side
3. Refresh SLOW marking

Legend

The cost break down below is per location and has been rounded up to the nearest £10

Location A1 = £240

Location A2 = £1030

Location B1+B2 = £200

Location C = £450

Location D = £290

Location E = £110

Location F = 1050

Location G = £540

Sub Total = £3910

Maintenance 20% = £780

Contingency 20% = £780

Final estimate = £5470

For Consultation

Hampshire County Council

STUART JARVIS BSc DipTP FCIHT MRTPI: DIRECTOR OF ECONOMY, TRANSPORT & ENVIRONMENT

DESIGNER KH	SCHEME	Longstock	DRAWING TITLE	Longstock Overall Location Plan Suggestions & estimate for Parish Meeting
CAD		SO20 6DP		
CHECKED	JOB No. 155	tools.absorb.paddocks		
APPROVED	SCALE @ A3 NTS	DATE 09 March 2023	SHEET NUMBER 1 of 1	DRAWING NUMBER 155-LON-KH-23-1055	REV -

HCC CAD FILE: E:\5 Schemes\155 Longstock\1 dwgs\cad\1 090323 1055 ideas for meeteing - consult.dwg